Abstract of quantities for Horamavoo Tank.

No.	Items of work	Quantity	Per unit	Rate
	Bund.			
1	Cutting grips and clearing jungle	20	Grade	
2	Earthwork to bund including watering and tamping	5,700	C.yd.	
3	New stone revetment	596	,,	
4	Old stone revetment, removing and resetting ...	100	,,	
5	Turfing	5,064	S.yd.	
6	Providing and fixing new grade stone, complete ...	19	Each	
7	Do Index stone ...	19	,,	
8	Do B. M. stones ...	2	,,	
9	Do Regd. No. stene ...	1	,,	
10	Do Gauge stone ...	1	,,	
	Constructing 9" stone ware pipe sluice.			
1	Earthwork cut open the bund and refilling with watering and tamping	50	C.yd.	
2	Earthwork excavation for foundation	32	,,	
3	Surki concrete for filling in foundation ...	87	C.ft.	
4	Burnt brick in surki	162	,,	
5	Burnt stone slabs 6" roughly dressed	50	S.ft.	
6	Surki mortar plastering	2·24	Sqr.	
7	Rough stone work new	19	C.yd.	
8	Stone ware pipes 9" including carting, laying, etc....	25	R.ft.	
9	Drilling holes in slabs	4	Each	
10	Providing and fixing wooden plug and iron rods, etc.	1	No.	
	Constructing waste weir.			
1	Earthwork excavation for foundation	53	C.yd.	
2	Surki mortar concrete	225	C.ft.	
3	Burnt brick in surki mortar	276	,,	
4	Burnt stone slabs roughly dressed and fixed ...	323	S.ft.	
5	Surki mortar plastering	3·00	Sqr.	
6	New stone apron with jelly packing	40	C.yd.	
7	Draft clearing	56	,,	

H. R. VENKATASUBBA RAO,
Executive Engineer.

KOLAR DIVISION.

Dated 30th November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 3rd January 1928, for restoring Beechagowdanahalli Hongekere tank, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees one thousand and two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Beechagowdanahalli Hongekre tank, Kolar Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender, will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating percentage less than the lowest tender or as per estimated rates will be accepted.

10. Once the tender has been accepted, no claim for any concessions for higher rates will be entertained.

11. The tenderers must quote specific rates for each item of work both in figures and words.

Abstract estimate of the probable cost of Restoring Beechagowdanahalli, Hongekere tank, Kolar Taluk.

Items of work	Per	Quantity	Rate	Cost	Total
Bund to R. L. 59·00.					
1. Earthwork to bund watering and tamping including lift and lead, etc., complete.	C.yds.	25,600			
2. Rough stone revetment new	,,	3,628			
3. Old stone revetment	,,	330			
4. Turfing	Sq. yd.	11,269			
5. Clearing silt from bed of breach ...	C.yds.	1,250			
6. Cutting steps earthwork and using for scour.	,,	369			
7. Cutting puddle trench and using for scour.	,,	121			
8. Filling breach with good earth, including watering and tamping, lead lift, etc., complete.	,,	3,710			
9. Puddle wall	,,	529			
10. Providing grade and index stones with bed stones and chistling, etc., complete.	Each	35			
11. Providing Register No. and inscription stone.	,,	1			
12. Bench mark stones, complete... ...	,,	2			

Items of work	Per	Quantity	Rate	Cost	Total
13. Gauge stones	Each	1			
14. Date stone	"	1			
15. Clearing jungle including removal of roots prickly pear and ant-hills, etc., and cutting trenches.	Each grade	24			
16. Baling water in trench	Lump sum				
17. Providing gravel backing behind revetment.	C.yds.	1992			
Total ...	...	...			
Constructing masonry sluice at R. L. 45·00 one at left and another at right of breaches.					
1. Earthwork cutting bund	C.yds.	49			
2. Surki concrete	C.ft.	286			
3. Burnt brick in surki mortar	"	888			
4. Burnt stone slabs dressed	S.ft.	358			
5. Surki plastering	Sqr.	9·67			
6. Providing locking arrangements ...	L. S.	...			
7. Clay filling to sides of masonry ...	C.yd.	10			
8. Cutting orifices	Each	3			
Total for one sluice ..	...	...			
For two sluices ...	...	...			
Left waste weir 95′ R. L. 53·00.					
1. Earthwork excavation for foundation chargeable to bund.	C.yd.	..			
2. Surki concrete	C.ft.	479			
3. Burnt stone in surki mortar sized stones ..	"	4,462			
4. Burnt stone slabs 6″ thick and dressed ..	S.ft.	580			
5. Providing joggles...	Each	35			
6. Cement pointing	Sqr.	15·10			
7. Burnt stone Sujeecut apron	C.yd.	351			
8. Jelly filling	"	422			
9. Clearing site	L. S.	...			
Total ...	...	...			
Right waste weir 150 feet long R. L. 53·00.					
1. Earthwork excavation chargeable to bund .	C.yd.	...			
2. Surki concrete	C.ft.	537			
3. Burnt stone in surki mortar	"	2,832			
4. Burnt stone slabs 6″ thick dressed ...	S.ft.	652			
5. Providing joggles	Each	40			
6. Cement pointing	Sqr.	11·10			
7. Rough stone work new	C.yd.	218			
8. Jelly filling	"	111			
9. Clearing site	L. S.	...			
Total ..	...	...			

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE SPECIAL DIVISION.

Notice dated 24th November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 17th December 1928, till 12 noon, for constructing outhouses and workshops attached to the Institute for Defectives in Mysore. An abstract of approximate quantities are given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.